

球阀 Ball valve



0.5

国家高新技术企业 浙江省著名商标
www.cndonjoy.com



东正一直致力于重大技术进步，是您值得信赖的事业伙伴！
Donjoy committing to major technological advances, is your reliable business partner!

0.1	自控调节阀+控制器 Automatic control regulating valve +Control head
0.2	生物制药隔膜阀 Biopharmaceutical diaphragm valve
0.3	高洁净泵 High purity pumps
0.4	防混蝶阀+蝶阀 Mixing proof butterfly valve + Butterfly valve
0.5	球阀 Ball valve
0.6	截止换向阀+防混阀+罐底阀 Divert seat valve+Mixing proof valve + Tank bottom valve
0.7	角阀+截止阀 Angle seat valve+Globe valve
0.8	止回阀+恒压阀+安全阀+减压阀 Check valve+constant pressure valve+safety valve +air release valve
0.9	清洁技术+取样阀+视镜+照明技术 Clean technology+sample valve+sight glass +lighting technology
0.10	过滤器+人孔 Filter+man hole cover/manway
0.11	卫生管件 Sanitary fittings ASME BPE DIN11852 B64823 SMS ISO IDF 3A



注意：
目录技术资料仅供设计参考。
设计更新和技术升级恕不另行通知！

不断革新技术、日新月异的市场发展和客户需求是当今我们面临的巨大挑战。面对这些挑战我们信心十足。因为东正高度专业化的产品和技术创新，是我们未来将以更高、更优的产品来满足不断增长的市场需求。

Technological innovation, rapid development of the market and customer needs are the greatest challenges facing us today. Facing with these challenges we are confident, because of highly professional products and technological innovation, we will meet the growing demand of market and customer with our better products.

法律声明
目录样册版本属东正所有，如有抄袭东正将追究其法律责任和经济赔偿。
东正众多技术设计，都具有专利保护，如有抄袭，东正必将追究法律责任和经济赔偿。

关于东正 About DONJOY



温州滨海经济开发区生产基地
Wenzhou binhai economic development zone production base

东正创立于1993年，注册资金5508万，是一家专注于研发高品质PID过程控制器、阀门定位器、流量控制器、阀门控制单元、高洁净过程控制阀、智能自控阀、高洁净泵、高洁净管材和管道配件。公司高度专业化的产品和技术专注于生物制药、食品饮料、酿酒、精细化工等工业领域。东正众多的创新解决方案，对满足全球，尤其是新兴市场不断增长生物制药和食品饮料行业的需求起到了积极作用。

东正制造的产品原材料、加工技术、焊接技术、表面处理等技术指标均已达到国内外先进水平。且符合ASME BPE、EHEDG、FDA、3A等一系列国际标准和规范要求，先后通过了由德国TÜV机构实施的欧盟承压设备指令(PED-97/23/EC)和(MD-06/42/EC)认证、美国 3A机构实施的3-A卫生标准认证、中国安全阀特种制造设备(TS)许可证和中国质量认证中心CQC ISO9001:2008质量管理体系认证等多项国际权威认证。

东正凭借先进的技术、优异的品质和完善的售后服务体系，先后被评定为国家高新技术企业，省著名商标、省科技型企业、创新型企业、专利示范企业、研发中心企业，守合同重信用AAA 业等众多荣誉。

温州空港经济园区生产基地
Wenzhou airport economic zone production base

占地面积25000m²，总投资1.2亿元，该基地建成后预计年可实现销售额5亿元。生产基地，引进ABB工业机器人，日本马扎克5轴加工中心。ABB机器人抛光设备。

Covering an area of 25000 m², with total investment after construction is expected to 120 million yuan, the base to achieve sales of 500 million yuan. Production base, introduces new ABB industrial robot, Japan mazak 5-axis center grams of five axis machining center, ABB machine polishing equipment.



Donjoy was built up in 1993, with registered capital RMB 55.08 millions. We focus on developing high quality PID process controller, the valve positioner, the flow controller, the valve control unit, high purity process control valve, intelligent self-control valve, high purity pump, high purity tubing fitting and pipeline accessories. Donjoy's products and technologies are widely used in biopharmaceutical, food, drink, wine fine chemicals and other industrial fields. Donjoy's innovation solutions meet the growing demand of the industry of biopharmaceutical, food and beverage from the whole world, especially the emerging market.

Raw material, processing technology, welding technology, surface treatment from Donjoy have achieved advanced levels of domestic and foreign market. Donjoy productions according to ASME BPE, EHEDG, FDA and 3A standard, get certificate of PED-97/23/EC and MD-06/42/EC issued by TÜV, 3A issued by 3A organization, TS licence and ISO9001:2008.

Donjoy with advanced technology, excellent quality and perfect after-sales service system, has been assessed as the national high-tech enterprises, the Provincial Famous Trademark, the Provincial Science and Technology Enterprises, Innovative Enterprises, Patent Model Enterprises, R & D Center, AAA Credit Enterprises.

制造与检验 Manufacturing and testing



机器人生产线

DONJOY以科学技术是第一生产力，也是企业核心竞争力，只有不断投入核心技术研发和创新，不断追求卓越，精益求精，以先进生产设备，严格的质量管理体系，精密的生产检测流程，保证每一款产品优良的性能。

Science and technology constitute a primary productive force, also the core competitive strength of the enterprise. Continuously intensifying the research, development and innovation of core technology, pursuing prominence and keeping improving, ensuring the excellent quality and performance of every single product by advanced production equipment, strict quality control and precise production and inspection procedures.

荣誉与资质 Honor and qualification

	3A 东正是美国3A认证组织的成员，3A是一个自愿组织，致力于维护公共卫生和奶制品产品质量通过独特的行业监管程序的设备，用于处理乳制品的卫生标准3A认证。东正通过认证产品，阀门系列(54-02)证书号(1580)，泵系列(02-10)证书号(1579)，管件(63-03)证书号(1581)等多种规格型号。
	PED/97/23/EC & MD/06/42EC 东正通过了TUV NORD吹共体压力容器97/23/EC质量保证模式H&M材料(管件)制造认证。 阀门证书 NO.CE 0036 泵类证书 NO.705201402401-00
	FDA177.2600 东正生产的阀门和泵以及流体设备等，与物料接触密封圈全部通过或符合美国食品和药品管理局和联邦法规第21条即，CFR 21 FDA177.2600和FDA177.1550认证，其涵盖： EPDM VITON(FPM) SILICON HNBRTPE橡胶塑料材料等。
	ISO9001/2008 东正通过中国质量认证中心CQC，ISO9001-2008/GB/T19001-2008企业质量管理体系认证。其证书编号：00108Q24215R1M/3302
	卫生许可证 东正通过了省卫生厅卫生阀门、卫生管件等检验，且获得了其颁发的证书，其编号：So083。 其许可证为国家出台的生活饮用水卫生监督管理方法证书。
	高新技术企业 东正通过多年发展和技术创新已获得多项国家发明专利，100多项实用新型专利，现已成为国家高新技术企业。
	浙江省著名商标 东正09年获得了温州市著名商标，2012年获得了浙江省著名商标。

DONJOY不但拥有以上认证和荣誉，且被评定为省科技型、创新型、专利示范、研发中心、守合同守信用企业等众多的荣誉证书。

DONJOY Ball valve
www.cndonjoy.com



蝶式球阀 Butterfly-type ball valve



应用

- ◆该蝶式球阀使用于任何过程控制的管道和设备上，特别适用于酿酒工业发酵罐上。

Applications

- ◆The butterfly-type ball valve is installed in any to pipeline and equipments for to controlling. It is specially used in brewing industry.

操作原理 Operating principles

- ◆无需维护
- ◆比其他的阀门更小更轻
- ◆操纵扭矩小
- ◆可排泄
- ◆垫圈根据FDA 177.2600
- ◆不管流体是何流向，手柄可以安装在侧边的阀体上。
- ◆不管是何种连接方式，阀体都可进行更换，而不会改变阀门的总长度。
- ◆Free maintenance
- ◆Portable and compact
- ◆Small torque moment
- ◆Drainable
- ◆Gasket complies with FDA 177.2600
- ◆Handle can be installed on the side of the valve body, no matter of the flow direction.
- ◆Valve body can be replaced in any connections. And the length will not change.



材质 Materials

- ◆物料接触部位: AISI304/316L
- ◆垫圈: EPDM(标准)
- ◆球座: PTFE
- ◆内表面: Ra0.8 μm
- ◆内表面: CNC车床加工

- ◆Part contacted with media AISI304/316L
- ◆Gasket: EPDM(Standard)
- ◆Seal: PTFE
- ◆Inner side polish: Ra0.8 μm
- ◆Out side polish: CNC lathe machining

技术规范

- ◆最大温度: 121°C(EPDM)
- ◆压力: 10bar

选项 Options

- ◆连接: 螺纹、卡箍、焊接、DIN、SMS、IDF、RJT、FIL
- ◆垫圈: NBR、VITON(FPM)、SILICON FDA 177.2600
- ◆位置传感器手柄、多定位手柄、拉杆手柄
- ◆铝制气动执行、不锈钢气动、电动执行器
- ◆智能控制器(C-TOP): AS-I 总线连接、电子连接

- ◆Connection ends: thread, clamp, weld, DIN, SMS, IDF, RJT, FIL
- ◆Gasket: NBR, VITON(FPM), Silicone FDA 177.2600
- ◆Manual: Multi-position handle, Pulling Stainless steel handle
- ◆Pneumatic: Aluminum electric actuator
- ◆Stainless steel electric/pneumatic actuator
- ◆Intelligent C TOP controls: AS-I connection, Electronic connection


Technical specification

- ◆Max temperature: 121°C(EPDM)
- ◆Pressure: 10bar

蝶式球阀扭矩表, 单位 (N.M)

SIZE	1"-3/4"	DN25/1"	DN32-1 1/4"	DN40/1.5"	DN50/2"	2.5"-DN65	3"	DN80	4"-DN100
扭矩	6	10	12	14	20	40	75	90	110

注意: 选择执行器建议增加20%安全余量



蝶式球阀 Butterfly-type ball valve



气动蝶式球阀+定位器 Pneumatic butterfly-type ball valve+positioner


SIZE: 1"-4", DN25-DN100
材质: 304/316L
电源: DC 24V
信号输入: 0/4-20mA, 0/5-10V
反馈输出: 4-20mA, 0-10V
防护: IP67

SIZE: 1" to 4", DN25 - DN100
Material: 304/316L
Power supply: DC 24V
Signal input: 0/4-20 mA, 0/5-10V
Output feedback: 4-20 mA, 0 to 10V
Protection: IP67

手动蝶式球阀 Manual butterfly-type ball valve


SIZE: 1"-4", DN25-DN100
工作温度: -10°C-130°C
工作压力: 10bar

CIP清洗口
Wash mouth



DIN							
SIZE	Dn	D	D1	L	H	K x K	螺纹(DIN) G1
DN10	9.7	13	34	72	40	8 x 8	R1/8 x 1/8"
DN15	16	19	34	72	40	8 x 8	R3/8 x 1/8"
DN20	19	22	34	72	40	8 x 8	R1/4 x 1/8"
DN25	25	28	50.5	72	44.5	8 x 8	R1/2 x 1/8"
DN32	31	34	50.5	83	46.5	8 x 8	R3/8 x 1/8"
DN40	37	40	64	87	55	10 x 10	R3/8 x 1/8"
DN50	49	52	64	101	64	10 x 10	R3/8 x 1/8"
DN65	66	70	91	125	80	11 x 11	R3/8 x 1/8"
DN80	81	85	106	145	93	11 x 11	R1/2 x 1/4"
DN100	97.4	104	119	185	106.5	14 x 14	R1/2 x 1/4"

INCH							
SIZE	Dn	D	D1	L	H	K x K	螺纹(SMS/RJT) G2 G3
1/2"	9.7	13	25.4	72	40	8 x 8	- -
3/4"	16.1	19.1	25.4	72	40	8 x 8	R3/8 x 1/8"
1"	22.4	25.4	50.5	72	41.5	8 x 8	R1/2 x 1/8"
1 1/4"	28.8	31.8	50.5	83	46.5	8 x 8	R3/8 x 1/8"
1 1/2"	35.1	38.1	50.5	87	55	10 x 10	R3/8 x 1/8"
2"	47.8	50.8	64	101	64	10 x 10	R3/8 x 1/8"
2 1/2"	59.5	63.5	77.5	121	75.5	11 x 11	R3/8 x 1/8"
3"	72.2	76.2	91	135	85.5	11 x 11	R3/8 x 1/8"
4"	97.6	101.6	119	185	106.5	14 x 14	R1/2 x 1/4"



DIN											
SIZE	Dn	D	L1	H1	H2	H3	H4	H5	M	LxW	L1xW1
DN10	9	12	125	43.5	172.5	309	140	141	86	158x71	165x120
DN15	15	18	125	43.5	172.5	309	140	141	86	158x71	165x120
DN20	19	22	125	43.5	172.5	309	140	141	86	158x71	165x120
DN25	25	28	125	43.5	172.5	309	140	141	86	158x71	165x120
DN32	31	34	125	43.5	172.5	309	140	141	86	158x71	165x120
DN40	37	40	125	43.5	172.5	309	167	141	86	158x71	165x120
DN50	49	52	144	47.5	172.5	309	157	141	86	190x81	212x134
DN65	66	70	160	50	248	385	192	164	113	213x98.5	212x134
DN80	81	85	257	52.5	285	422	204	206	133	259x108.5	259x166
DN100	100	104	397	52.5	306	431	230	206	166	259x108.5	259x166

INCH(3A, SMS, ISO/IDF, RJT, DS)											
SIZE	Dn	D	L1	H1	H2	H3	H4	H5	M	LxW	L1xW1
1/2"	9.7	12.7	126	43.5	172.5	309	140	141	86	158x71	165x120
3/4"	16.1	19.1	126	43.5	172.5	309	140	141	86	158x71	165x120
1"	22.4	25.4	126	43.5	172.5	309	140	141	86	158x71	165x120
1 1/4"	28.8	31.8	126	43.5	172.5	309	140	141	86	158x71	165x120
1 1/2"	35.1	38.1	133	47.5	172.5	309	157	141	86	158x71	165x120
2"	47.8	50.8	144	47.5	172.5	309	167	141	86	190x81	165x120
2 1/2"	59.5	63.5	160	50	248	385	192	164	113	207x94	165x120
3"	72.2	76.2	257	52.5	285	422	204	206	133	213x98.5	212x134
4"	97.6	101.6	397	52.5	306	431	230	206	166	259x108.5	259x166

无滞留球阀 Non-retention ball valve



应用

- ◆该球阀根据3A ASME BPE标准设计，主要应用于生物制药、食品饮料、酿酒、化工等工业领域。

技术特点

- ◆全包式球座设计，无滞留高洁净，满足CIP SIP杀菌和清洗要求，耐温180℃ 压力30bar 动补密封设计，具有扭矩小，寿命长等特点。
- ◆可配置各种执行结构，如电动、卧式气动、不锈钢立式气动、钥匙手动手柄，还可以加装控制单元、定位器、位置传感器等可兼容自动控制系统。

Applications


- ◆The ball valve according to 3A and ASME BPE standard design, mainly used in pharmaceutical, food and beverage, wine, chemical and other industries..

Technical characteristics

- ◆All-inclusive tee design, no stranded high clean, meet the requirement of CIP and SIP sterilization and cleaning, and heat resistance of 180 °C, the highest pressure 30 bar, automatic compensating sealing design, the advantages of small torque, long service life, etc.
- ◆Available with a variety of structures, such as electric pneumatic, stainless steel, horizontal vertical pneumatic, key manually handle, can also be equipped with the control unit, locator, position sensor and other compatible automatic control system.



球阀压力-温度曲线图
Pressure And Temperature Curve



直通无滞留球阀扭矩表, 单位 (N.M)

SIZE	1/2"-3/4"	DN25/1"	DN32-1 1/4"	DN40/1.5"	DN50/2"	2.5"-DN65	3"	DN80	4"-DN100
扭矩	6	10	12	14	20	40	75	90	110

注意: 选择执行器建议增加20%安全余量

表面处理

◆所有的表面CNC 0.8μm 达到RA0.4μm 电抛光
可达到0.25μm

Surface finish

◆CNC machining all surfaces to 0.8μm, polishing can be achieved RA0.4μm, electro-polishing can reach 0.25μm

Conversion Table of Surface Finishes

Surface Designation	GRIT	Mechanically Polished			
		Ra Average		Ra Max	
ASME BPE		μ-in	μ-m	μ-in	μ-m
SFV 1	GRIT 320	15	0.375	20	0.50
SFV 2	GRIT 240	20	0.50	25	0.625
SFV 3	GRIT 180	25	0.625	30	0.75

Surface Designation	GRIT	Mechanically and Electropolished			
		Ra Average		Ra Max	
ASME BPE		μ-in	μ-m	μ-in	μ-m
SFV 4	GRIT 320	10	0.25	15	0.375
SFV 5	GRIT 240	15	0.375	20	0.50
SFV 6	GRIT 180	20	0.50	25	0.625

无滞留球阀 Non-retention ball valve



气动三片无滞留球阀 Pneumatic three-piece non-retention ball valve

规格: 1/2"-4", DN10-DN100
可选位置反馈
Size: 1/2"-4" DN10-DN100
Optional position feedback



气动球阀-MINI C-TOP Pneumatic ball Valve +MINI C-TOP

SIZE: 1/2"-1. DN10-DN25



气动无滞留球阀+定位器 Pneumatic non-retention ball valves+valve positioner

规格: 1/2"-4", DN10-DN100
输入: 0/4-20mA, 0-5/10V
输出: 0/4-20mA, 0-5/10V(位置反馈)
总线: DEVICE NET BUS 通讯
单作用/双作用

Size: 1/2"-4", DN10-DN100
Input: 0/4-20mA, 0-5/10V
Output: 0/4-20mA, 0-5/10V
(Position feedback)
Bus: DEVICE NET BUS
Single/double action



气动球阀+控制单元 Pneumatic ball Valve+C-TOP

电源: DC 24V ± 10%
PLC连接自动化控制
单作用/双作用
基本版: 接线端子连接
总线: AS- I 总线 通讯(选项)

Power: DC 24V ± 10%
PLC Connection automatically control
Single/double action
Basic version: terminal block
Bus version: AS- I DEVICE NET BUS(options)



电动无滞留球阀 Electric non-retention ball valve

开关型
智能型(4-20mA)
位置反馈型
电源 DC:24V

Switching type
Intelligent(4-20mA)
Position feedback
Power DC:24V



卧式气动无滞留球阀+定位器
Pneumatic non-retention ball valves+valve positioner

规格: 1/2"-4", DN10-DN100
输入: 0/4-20mA, 0-5/10V
输出: 0/4-20mA, 0-5/10V (位置反馈)
总线: DEVICE NET BUS 通讯
单作用/双作用
Size: 1/2"-4", DN10-DN100
Input: 0/4-20mA, 0-5/10V
Output: 0/4-20mA, 0-5/10V (Position feedback)
Bus: DEVICE NET BUS
Single/double action



规格: DN10-DN100
材质: 304/316L
工作温度: -10°C-150°C
气源压力: 4-7bar
连接方式: 卡箍、焊接、法兰、螺纹
SIZE DN10-DN100
Material: 304/316L
Working temperature: -10 °C to 150 °C
Air pressure: 4 to 7 bar
Connection mode: clamp, welding, flange, screw thread



气动三片式无滞留球阀
Pneumatic three-piece non-retention ball valve

整体CNC加工, 外观具有无死角。
SIZE: 1/2", DN10-DN50
材质: 304/316L




SIZE	A	ISO5211
0.5"-1 1/4"	6	FM
1.5"-2"	10	FM
2.5"-3"	12	FM
4"	12	FM

注意: 可任意配置各种执行机构球阀




SIZE	A/A	ISO5211
1/2"-3/4"	11*11	FM-05
1"-1.5"	14*14	FM-05
2"	17*17	FM-07
2.5"-3"	22*22	FM-07
4"	27*27	FM-10

无滞留球阀 Non-retention ball valve




INCH														
SIZE	ISO5211	ΦDn	ΦD	ΦD1	L	H	A	H1	A1	H2	A2	H3	A3	AA/132
0.5"	FM	9.7	12.7	25.4	89	75	153	175.5	158	220	165	226	86	6
0.75"	FM	16.1	19.1	25.4	89	75	163	175.5	158	220	165	226	86	
1"	FM	22.4	25.4	50.5	114	78	163	179	158	223	165	230	86	
1.25"	FM	28.8	31.8	50.5	117	83	163	198	190	228	165	235	86	
1.5"	FM	35.1	38.1	50.5	142	94	164	206	190	236	165	243	86	10
2"	FM	47.8	50.8	64	156	99	164	237	207	255	165	315	113	
2.5"	FM	59.5	63.5	77.5	197	116	236	257	207	272	212	332	113	
3"	FM	72.2	76.2	91	221	127	236	274	213	314	212	380	133	
3.5"	FM	85	89	106	229	133	236	291	259	354	259	386	133	12
4"	FM	97.6	101.6	119	241	150	236	308	259	371	259	423	166	

DIN														
SIZE	ISO5211	ΦDn	ΦD	ΦD1	L	H	A	H1	A1	H2	A2	H3	A3	AA/132
DN10	FM	9	12	34	89	75	153	175.5	158	220	165	226	86	6
DN15	FM	15	18	34	89	75	163	175.5	158	220	165	226	86	
DN20	FM	19	22	34	89	75	163	175.5	158	220	165	226	86	
DN25	FM	25	28	50.5	114	78	163	179	158	223	165	230	86	
DN32	FM	31	34	50.5	117	83	163	198	190	228	165	235	86	10
DN40	FM	37	40	50.5	142	91	164	206	190	236	165	243	86	
DN50	FM	49	52	64	156	99	164	237	207	255	165	315	113	
DN65	FM	66	70	91	207	122	236	269	213	309	212	338	113	
DN80	FM	81	85	106	229	133	236	291	259	354	259	386	133	12
DN100	FM	100	104	119	241	150	236	308	259	371	259	423	166	



NO. VQW120S1



NO. VQW140S1

内螺纹球阀 Thread ball valve

SIZE	ISO5211	L2	H	A	G	BSP1	W1
0.5"	F04	79	75	163	1/2"	1/2"	162
0.75"	F04	83	75	163	3/4"	3/4"	164
1"	F04	90	78	163	1"	1"	164
1.25"	F04	107	83	163	1.25"	1.25"	164
1.5"	F05	114	91	164	1.5"	1.5"	164
2"	F05	133	99	164	2"	2"	164
2.5"	F07	157	116	236	2.5"	2.5"	236
3"	F07	179	127	236	3"	3"	236

法兰球阀 Flanged Ball Valve

SIZE	ISO5211	ΦD1	ΦD2	ΦA	n-Φd	L	H	A
DN15	F04	15	95	65	4-14	130	75	163
DN20	F04	19	105	75	4-14	150	75	163
DN25	F04	25	115	85	4-14	160	78	163
DN32	F04	31	140	100	4-18	180	83	163
DN40	F05	37	150	110	4-18	200	91	164
DN50	F05	49	165	125	4-18	220	99	164
DN65	F07	66	185	145	4-18	250	122	236
DN80	F07	81	200	160	8-18	280	133	236
DN100	F10	100	220	180	8-18	320	150	236

罐底球阀


Ball valve at the tank bottom



应用

Applications


- ◆ The ball valve is a specially designed applied to pressure vessels and equipment, including tank emptying and feeding of tank bottom valve, turnkey tee and sealing automatic compensation design, therefore, with the high pressure and high temperature resistant, torque, etc, the characteristics of long service life, content with CIP and SIP cleaning and sterilization. Very suitable for application in high clean technology system such as biological pharmacy, food and beverage, dairy products, chemical and other fields.
- ◆ A configurable various actuators, such as electric, pneumatic, manual interchangeable.



罐底三片式无旁通球阀
NO. VQW120S1-06

SIZE	ISO5211	ΦDn	ΦD	ΦD2	L1	H	A
DN40 1.5"	F05	35.1	38.1	140	121	91	164
DN50 2"	F05	47.8	50.8	140	136	99	164
DN65 2.5"	F07	59.5	63.5	180	164	116	236
DN80 3"	F07	72.2	76.2	200	164	127	236

各种进出口连接方式



三通无滞留球阀 Three-way non-retention ball valve





应用 Applications

该阀卫生设计，在食品加工、饮料、果汁、酿酒、生物制药等领域有着广泛的应用。三通球阀，具有非常灵活的组合，例如，L型和T型可在现场更换，进出口方向可任意组合变化都保证零死角、零滞留。


The hygienic design of the valve is widely used in the field of food processing, beverages, fruit juices, wine, biopharmaceutical and vary flexible body combinations. For example, L-Port or T-Port can be interchangeable on-site. Inlet, outlet to be any combination of changes can guarantee dead angle, no retention.

技术规范 Technical Specifications

规格: 1"-4", DN25-DN100
材质: 1.4301/304, 316L/1.4404
垫圈: PTFE, FPM (FDA 177.1550)
最高温度: -20°C到150°C(标准) -30°C到200°C(选项)
压力范围: 10-30bar(取决于密封材质和温度)
操作方式: 手动、气动、电动
表面处理: 内表面Ra0.6 μm, 外部喷砂
认证: PED/97/23/EC, 3A, FDA
自控配置: 过程控制器/阀门定位器, 0/4...20mA, 0-5/10V(详见控制器目录)(选项) 阀门底部控制单元, AS-I 总线通讯, 接线端子连接(选项) 位置传感器PNP NPN(选项)
Size: 1"-4", DN25-DN100
Material: 1.4301/304, 316L/1.4404
Gaskets: PTFE/FPM (FDA 177.1550)
Temperature: -20°C to 150°C (Standard)
-30°C - 200°C (Option)
Pressure: 10-30bar (Depending on seal material and temperature)
Operating modes: manual, pneumatic, electric
Surface finishing: Internal surface Ra0.6 μm, external surface sand blast.
Certificate: PED/97/23/EC, 3A, FDA
Control: process controller valve positioning (see controller directory)
C-TOP control unit, AS-I Device Net bus communication terminal connection (options), position sensor PNP, NPN (options)



该球阀有四个方向通道(如图1、2、3、4)。我们可以根据客户需求，安装不同方向上不同数量的法兰。
The ball valve has 4 directions (Figure 1, 2, 3, 4) according to the customer, needs to install different number of flange in direct direction.



T型球芯 T-Port

L型球芯 L-Port

三通无滞留球阀 Three-way non-retention ball valve



气动无滞留球阀+定位器 Pneumatic three-way ball Valve + valve positioner

规格: 1/2"-4", DN10-DN100
输入: 0/4-20mA, 0-5/10V
输出: 0/4-20mA, 0-5/10V (位置反馈)
总线: DEVICE NET BUS 通讯
单作用/双作用
SIZE: 1/2"-4", DN10-DN100
Input: 0/4-20mA/0-5/10V
Output: 0/4-20mA/0-5/10V (Position sensor)
Bus: DEVICE NET BUS
Air/Spring, Air/Air



不锈钢气动球阀 Pneumatic three-way ball valve+C-TOP

气动球阀+C-TOP
电源: DC 24V ± 10%
PLC连接自动化控制
单作用/双作用(选项)
基本版: 接线端子连接
总线: AS-I 总线 通讯(选项)
Pneumatic ball valve+C-TOP
Power DC 24V ± 10%
PLC Connection automatically control
Single/double action (options)
Basic version: terminal block
Bus version: AS-I BUS
Device Net (options)



电动三通球阀 Electric three-way ball valve

开关型
智能型(4-20mA)
位置反馈型
电源 DC 24V
On/off type
Intelligent (4-20mA)
Position sensor
Power DC 24V




气动三通球阀 Pneumatic three-way ball valve

任意配置执行机构
三通球阀

卡箍无滞留球阀 Non-retention ball valve

操作扭矩(N.m.) Operating Torque(N.m.)							
SIZE	DN25-1"	DN40-1.5"	DN50-2"	2.5"-3"	DN65-3"	DN80	4"-DN100
扭矩	15	25	35	50	75	105	120

注意：选择执行器建议增加20%安全余量



INCH													
SIZE	ISO5211	ΦDn	ΦD	ΦD1	L	H	A	H1	A1	H2	A2	H3	A3
1"	F04F05	22.4	25.4	50.5	148	62	165	210	190	240	165	247	86
1.25"	F04F05	28.8	31.8	50.5	152	65	165	215	207	245	165	252	86
1.5"	F05F07	35.1	38.1	50.5	180	100	165	234	207	252	165	312	113
2"	F05F07	47.8	50.8	64	196	106	165	252	213	271	165	331	113
2.5"	F07F10	59.5	63.5	77.5	252	116	236	274	213	314	212	380	133
3"	F07F10	72.2	75.2	91	284	137	236	341	259	335	212	402	133
4"	F07F10	97.6	101.6	119	323	165	236	396	287	565	259	448	165

DIN													
SIZE	ISO5211	ΦDn	ΦD	ΦD1	L	H	A	H1	A1	H2	A2	H3	A3
DN25	F04F05	25	28	50.5	148	62	165	210	190	240	165	247	86
DN32	F04F05	31	34	50.5	152	65	165	215	207	245	165	252	86
DN40	F05F07	37	40	50.5	180	100	165	234	207	252	165	312	113
DN50	F05F07	49	52	64	196	106	165	252	213	271	165	331	113
DN65	F07F10	66	70	91	264	132	236	298	213	328	212	394	133
DN80	F07F10	81	85	106	300	145	236	376	287	545	259	426	165
DN100	F07F10	100	104	119	323	165	236	396	287	565	259	448	165



卡箍无滞留球阀
Clamp Non-retention Ball Valve




应用 Applications

无滞留球阀为全包式球座设计，解决了球阀液体滞留阀腔内的问题，该球阀适用于生物制药工程。

Overall valve body design prevents the medium from retaining in the valve after flowing through the body. This kind of ball valve is applied to pharmacy and biotechnology industries.

设计和特点 Design and Features

- ◆ 阀体组合卡箍连接
- ◆ 无需专业工具即拆卸阀门
- ◆ 操作扭矩小
- ◆ 垫圈根据FDA 177.2600
- ◆ 连接：卡箍、焊接、螺纹、DIN、SMS、ISO、IDF、BPE、RJT
- ◆ 无论是何种连接方式，阀体都可进行更换，而不会改变阀门的总长度
- ◆ Valve bodies Combined with clamp connection
- ◆ Easy disassemble without special tools
- ◆ Small Operating torque
- ◆ Gasket complies with FDA 177.2600
- ◆ Connection: clamp, weld, thread, DIN, SMS, ISO, IDF, BPE, RJT
- ◆ Valve body can be replaced in any connections. And Valve length will not change



SIZE	A	L	H	B	Dn
DN15	90	105	65	34.0	15
DN20	100	105	65	34.0	16
DN25	110	105	70	50.5	25
DN32	120	130	80	50.5	31
DN40	140	150	90	50.5	37
DN50	164	160	95	64.0	49
DN65	180	180	110	91.0	66

SIZE	A	L	H	B	Dn
Φ19	90	105	65	25.4	16.0
Φ25	110	105	70	50.5	22.4
Φ32	120	105	80	50.5	28.8
Φ38	140	130	90	50.5	35.1
Φ51	164	150	95	64.0	47.8
Φ57	170	160	110	77.5	53.0
Φ63	180	180	110	77.5	59.5

直通球阀 Direct way ball valve



阀腔清洗口



三通球阀
1"-4", DN25-100



直通球阀
1/2"-4", DN10-100

应用 Applications

无论是手动还是自动操作球阀，主要应用于加工饮料、酿酒、炼油、化妆品和化学工业。

It is widely used in beverage, brewing, oil refinery, cosmetic, chemical industries...

设计和特点 Design and Features

- ◆ 无需维护
- ◆ 比其他的阀门更小更轻
- ◆ 操纵扭矩小
- ◆ 垫圈根据PTFE FDA 177.2600
- ◆ 无论液体是何种流向，手柄可以安装在侧边的阀体上
- ◆ 无论是何种连接方式，阀体都可更换，而且不会改变阀门的总长度
- ◆ 连接：螺纹、焊接、卡箍、法兰、DIN、SMS、RJT、FIL
- ◆ 可装配气动执行器，电动执行器
- ◆ 物料接触部位 AISI, 304/316L
- ◆ 其它部位 AISI 304
- ◆ 认证：PED, 97/23EC
- ◆ Free of maintenances
- ◆ Compact and portable
- ◆ Small operating torque
- ◆ Gasket complies with PTFE FDA 177.2600
- ◆ Hand lever can be installed on the side of the valve body, no matter of the flow direction.
- ◆ Connection ends: thread, clamp, weld, flange, DIN, SMS, RJT, FIL.
- ◆ It can be installed with pneumatic and electric actuators.
- ◆ The part contacted with media is AISI 304/316L
- ◆ Other parts AISI 304
- ◆ Certifications: PED, 97/23/EC

选项 Options

- ◆ 球芯类型：T型、L型
- ◆ 带清洗排泄口
- ◆ 材质：AISI 304 316L
- ◆ Ball: T port, L port
- ◆ With cleaning and drainage port
- ◆ Material: AISI 304, 316L

球阀 Ball valve



气动球阀+定位器

流量调节式球阀
输入/输出: 0/4-20mA
1"-4", DN25-DN100
Pneumatic ball valve+
Positioner
Flow regulating valve
Input/output: 0/4-20mA
1"-4", DN25-DN100



卧式气动三通球阀

SIZE: 1/2"-4",
DN10-DN100
连接方式：卡箍、螺纹、
焊接
Horizontal pneumatic
ball valve
1/2"-4", DN10-DN100
Connection: welding,
clamp, thread, etc.



卧式气动球阀 +定位器

流量调节式球阀
输入/输出: 0/4-20mA
电源: DC24V
支持总线: DEVICE NET BUS
防护: IP67
SIZE: 1"-4", DN25-DN100
Pneumatic ball valve+
positioner
Flow regulating valve
input/output: 0/4-20mA
1"-4", DN25-DN100



气动球阀 +控制单元

1/2"-1", DN10-DN25
材质: 304/316L
电源: DC24V
总线: AS-I BUS
详细请查阅自控目录手册
Pneumatic Valve +
MINI-C-TOP
SIZE 1/2"-1", DN10-DN25
Material: 304 / 316L
Feedback Output: 0 / 4-
20mA / DC24V
Bus: AS-I BUS
For details, please consult
the controller catalog



气动球阀 +控制单元

SIZE: 1"-4", DN25-DN100
材质: 304/316L
电源: DC24V
总线: AS-I BUS
详细请查阅自控目录手册
Pneumatic Valve + C-TOP
SIZE 1/2"-1", DN10-DN25
Material: 304 / 316L
Feedback Output: 0 / 4-
20mA / DC24V
Bus: AS-I BUS
For details, please consult
the controller catalog




电动球阀开关型:


Electric valve
Switch type:
Output electrical signal, valve
position lights in place
Modulating
Input: 4-20mA
Feedback Output: electrical
Power: DC24V AC110V / 220V
Explosion levels: EXDII BT4
(option)



三通球阀流体示意图 Ball Type



T型球芯 T Port



L型球芯 L Port



DONJOY创新支架 专利保护

该支架可满足于各种电动、立式气动、卧式气动等多种执行器

ISO5211安装

手动、气动易互换

DONJOY innovative stent patent protection
The bracket can meet a variety of electric, pneumatic, vertical, horizontal pneumatic and other actuators.
ISO5211 installation
Pneumatic manual interchangeable

直通球阀操作扭矩(N.m.) Operating Torque(N.m.)

SIZE	1/2"-3/4"	DN25~1"	DN32~1.1/4"	DN40~1.5"	DN50~2"	2.5"-DN65	3"	DN80	4"-DN100
扭矩	6	8	10	12	18	35	65	75	80

注意：选择执行器建议增加20%安全余量


三通球阀操作扭矩(N.m.) Operating Torque(N.m.)

SIZE	DN25~1"	DN40~1.5"	DN50~2"	2.5"	DN65~3"	DN80	4"-DN100
扭矩	12	20	25	40	65	80	90


注意：选择执行器建议增加20%安全余量

直通球阀 Direct way ball valve


手动球阀尺寸图
Manual ball valve Dimension




焊接式
NO.VOC100S1



卡箍式
NO.VOC110S1



DIN螺纹
NO.DIN-VOC130S1



SMS螺纹
NO.SMS-VOC130S1




DIN直通 Direct way ball valve

Size	Dr	D	D1	A	H	J	螺纹G1/1(Dr)
DN10	9.7	13	34	95	58	126.5	Rd329 × 1/8"
DN15	16	19	34	95	58	126.5	Rd334 × 1/8"
DN20	19	22	34	95	58	126.5	Rd444 × 1/8"
DN25	25	28	50.5	100	68	126.5	Rd52 × 1/8"
DN32	31	34	50.5	108	70	126.5	Rd558 × 1/8"
DN40	37	40	50.5	123	83	164.5	Rd65 × 1/8"
DN50	49	52	64	136	89	164.5	Rd78 × 1/8"
DN65	66	70	91	162	113	184.5	Rd95 × 1/8"
DN80	81	85	106	180	123	233	Rd110 × 1/4"
DN100	100	104	119	206	137	233	Rd130 × 1/4"

INCH直通 Direct way ball valve

Size	Dr	D	D1	A	H	J	螺纹G1/1(Dr)
1/2"	9.7	12.7	25.4	95	58	126.5	—
3/4"	16.1	19.1	25.4	95	58	126.5	Rd36 × 1/8"
1"	22.4	25.4	50.5	100	68	126.5	Rd40 × 1/8"
1 1/4"	28.8	31.8	50.5	108	70	126.5	Rd48 × 1/8"
1 1/2"	35.1	38.1	50.5	123	83	164.5	Rd60 × 1/8"
2"	47.3	50.8	64	136	89	164.5	Rd70 × 1/8"
2 1/2"	59.5	63.5	77.5	150	113	184.5	Rd85 × 1/8"
3"	72.2	76.2	91	172	123	184.5	Rd96 × 1/8"
4"	97.5	101.6	119	206	137	233	Rd125 × 1/4"

气动球阀尺寸图
Pneumatic ball valve Dimension




DIN						
Size	Dn	D	H1	H2	M	LxW
DN10	9.7	13	224	183.5	86	158x71
DN15	16	19	224	183.5	86	158x71
DN20	19	22	224	183.5	86	158x71
DN25	25	28	244	193.5	86	158x71
DN32	31	34	246	195.5	86	158x71
DN40	37	40	272	232.5	86	158x71
DN50	49	52	260	241.5	86	190x81
DN65	66	70	360	291	113	213x96.5
DN80	81	85	407	312	133	259x108.5
DN100	100	104	442.5	327.5	166	259x108.5

INCH						
Size	Dn	D	H1	H2	M	LxW
0.5"	9.7	12.7	224.5	183.5	86	158x71
0.75"	16.1	19.1	224.5	183.5	86	158x71
1"	22.4	25.4	234.5	193.5	86	158x71
1 1/4"	28.8	31.8	236.5	195.5	86	158x71
1 1/2"	35.1	38.1	272	232.5	86	158x71
2"	47.8	50.8	280	244.5	86	190x81
2 1/2"	59.5	63.5	348	270	113	207x94
3"	72.2	76.2	402	296	133	213x96.5
4"	97.6	101.6	442.5	327.5	166	259x108.5

三通球阀 Three way ball valve


手动球阀尺寸图
Manual ball valve Dimension



DIN三通 Three links ball valve										
Size	Dn	D	D1	B	B1	H ₁	J	螺纹G1/2(DN6)		
DN10	9.7	13	34	136	88	73	126.5	Rd33 x 1/8"		
DN15	16	19	34	136	88	73	126.5	Rd34 x 1/8"		
DN20	19	22	34	136	88	73	126.5	Rd44 x 1/8"		
DN25	25	28	50.5	136	88	73	126.5	Rd52 x 1/8"		
DN32	31	34	50.5	136	71	74	126.5	Rd58 x 1/8"		
DN40	37	40	50.5	156	80	67	164.5	Rd65 x 1/8"		
DN50	49	52	64	170	90	61	164.5	Rd78 x 1/8"		
DN65	66	70	91	204	102	113	184.5	Rd95 x 1/8"		
DN80	81	85	106	226	118	124	233	Rd110 x 1/4"		
DN100	100	104	119	264	142	137	233	Rd130 x 1/4"		

INCH三通 Three links ball valve										
Size	Dn	D	D1	B	B1	H ₁	J	螺纹G1/2(SMS)		
1/2"	9.7	12.7	25.4	136	88	73	126.5	-		
3/4"	16.1	19.1	25.4	136	88	73	126.5	Rd36 x 1/8"		
1"	22.4	25.4	50.5	136	88	73	126.5	Rd40 x 1/8"		
1 1/4"	28.8	31.8	50.5	136	71	74	126.5	Rd48 x 1/8"		
1 1/2"	35.1	38.1	50.5	156	80	67	164.5	Rd60 x 1/8"		
2"	47.8	50.8	64	170	90	61	164.5	Rd70 x 1/8"		
2 1/2"	59.5	63.5	77.5	194	102	102	184.5	Rd85 x 1/8"		
3"	72.2	75.2	91	220	118	120	184.5	Rd98 x 1/8"		
4"	97.6	101.6	119	264	142	137	233	Rd125 x 1/4"		

气动球阀尺寸图
Pneumatic ball valve Dimension






DIN						
Size	Dn	D	Ha1	Ha2	M	LXW
DN10	9.7	13	239	198.5	86	156x71
DN15	16	19	239	198.5	86	156x71
DN20	19	22	239	198.5	86	156x71
DN25	25	28	239	198.5	86	156x71
DN32	31	34	240	213.5	86	190x81
DN40	37	40	276	251.5	86	190x81
DN50	49	52	339	261	113	207x94
DN65	65	70	365	296	113	213x98.5
DN80	81	85	434	319	198	259x128.5
DN100	100	104	450	335.5	198	259x128.5

INCH						
Size	Dn	D	Ha1	Ha2	M	LXW
0.5"	9.7	12.7	239	198.5	86	156x71
0.75"	16.1	19.1	239	198.5	86	156x71
1"	22.4	25.4	239	198.5	86	156x71
1 1/4"	28.8	31.8	240	213.5	86	190x81
1 1/2"	35.1	38.1	278	251.5	86	190x81
2"	47.8	50.8	339	261	113	207x94
2 1/4"	59.5	63.5	354	276	113	207x94
3"	72.2	76.2	407	301	133	213x98.5
4"	97.6	101.6	450	335.5	166	259x128.5

工业级阀门 Industrial valve



主要外形尺寸 Main size



薄型法兰球阀
Wafer Type Flanged Ball Valve


DN	d	L	D	K	D1	C	H	N-φ	W
15	15	35	95	65	45	10	65	4-M12	100
20	20	37	105	75	55	11	70	4-M12	110
25	25	42	115	85	65	12	80	4-M12	125
32	32	53	135	100	76	14	90	4-M16	150
40	38	62	160	110	85	16	96	4-M16	160
50	50	73	180	125	100	17	104	4-M16	180
65	58	90	195	145	118	18	110	4-M16	200

国标高平台法兰球阀(防火型)
GB Flange Ball Valve With High Mounting Pad(Fire Safe)

INCH	DN	L	D	K	D1	N-φ	C	W
1/2"	15	108	95	65	45	4-14	14	140
3/4"	20	117	105	75	55	4-14	14	140
1"	25	127	115	85	65	4-14	14	165
1 1/4"	32	140	135	100	78	4-18	16	165
1 1/2"	40	165	145	110	85	4-18	16	190
2"	50	178	160	125	100	4-18	16	210
2 1/2"	65	190	180	145	120	4-18	18	240
3"	80	203	195	160	135	8-18	20	260
4"	100	229	215	180	155	8-18	20	330
5"	125	266	245	210	185	8-18	22	520
6"	150	294	280	240	210	8-23	24	600
8"	200	457	335	295	265	12-23	26	800
10"	250	533	405	355	320	12-25	30	1000
12"	300	610	460	410	375	12-25	30	1200


日标高平台法兰球阀(防火型)
JIS Flange Ball Valve With High Mounting Pad(Fire Safe)

INCH	DN	H	W	L	D	K	D1	C	N-φ
1/2"	15	65	140	108	95	70	52	12	4-15
3/4"	20	72	140	117	100	75	58	14	4-15
1"	25	83	165	127	125	90	70	14	4-19
1 1/4"	32	90	165	140	135	100	80	16	4-19
1 1/2"	40	100	190	165	140	105	85	16	4-19
2"	50	110	210	178	155	120	100	18	4-19
2 1/2"	65	130	240	190	175	140	120	18	4-19
3"	80	140	260	203	185	150	130	18	8-19
4"	100	165	320	229	210	175	155	18	8-19
5"	125	250	400	306	250	210	185	20	8-23
6"	150	270	460	334	280	240	195	22	8-23
8"	200	320	600	407	330	290	265	22	12-23




三片式法兰球阀
3PC Flange Ball Valve

DN	B	L	H	W	D	K	D1	C	N-Φ	D	K	D1	C	N-Φ	D	K	D1	C	N-Φ
15	15	130	75	130	85	65	45	14	4-14	95	65	45	16	4-14	89	60.5	35	10	4-15
20	20	150	80	140	105	75	58	16	4-14	105	75	58	18	4-14	98	70	43	11	4-15
25	25	160	85	150	115	85	68	16	4-14	115	85	68	18	4-14	106	79.5	51	12	4-15
32	32	180	100	170	140	100	78	16	4-18	140	100	78	18	4-18	117	89	64	13	4-15
40	40	200	110	200	150	110	88	16	4-18	150	110	88	18	4-18	127	98.5	73	15	4-15
50	50	230	120	220	165	125	102	18	4-18	165	125	102	20	4-18	152	109.5	82	16	4-19
65	65	250	130	280	185	145	122	18	4-18	185	145	122	22	8-18	170	139.5	105	18	4-19
80	78	280	140	300	200	160	138	20	8-18	200	160	138	24	8-18	190	152.5	127	19	4-19
100	100	320	160	340	220	180	158	20	8-18	235	190	162	24	8-22	229	190.5	157	24	8-19



不锈钢内螺纹闸阀
Stainless steel female gate Valve


DN	G	L	E	B	H	W
15	1/2"	55	16	31	90	70
20	3/4"	60	18	36	96	70
25	1"	66	20	46	103	70
32	1 1/4"	76	21.5	56	123	80
40	1 1/2"	80	23	63	152	100
50	2"	93	24.5	76	163	100



美式内螺纹截止阀
American Type Female Globe Valve


DN	G	L	E	B	H	W
8	1/4"	65/68	15	25	80	70
10	3/8"	65/68	15	26	80	70
15	1/2"	65/65	16	31	88	70
20	3/4"	70/75	18	38	95	70
25	1"	80/90	20	46	110	80
32	1 1/4"	90/105	21.5	56	123	100
40	1 1/2"	100/120	23	63	135	100
50	2"	120/140	24.5	76	150	100

工业级阀门 Industrial valve




内螺纹止回阀
Female Check Valve

DN	G	L	E	B	H
8	1/4"	84	10	24	42
10	3/8"	84	10	24	42
15	1/2"	84	12	26	45
20	3/4"	80	17	32	53
25	1"	90	20	40	60
32	1 1/4"	105	20	51	64
40	1 1/2"	120	20	58	76
50	2"	140	23	69	82
65	2 1/2"	165	27	86	89



旋启式法兰止回阀
Flange Swing Check Valve

DN	PN16 DN150 L		D	K	D1	C	N-Φ	D	K	D1	C	N-Φ	D	K	D1	C	N-Φ
25	160	127	115	85	65	14	4-14	108	79.5	51	12	4-15	125	90	70	14	4-19
32	180	143	135	100	78	16	4-18	117	89	64	13	4-15	136	100	80	16	4-19
40	200	165	145	110	85	16	4-18	127	98.5	73	14.5	4-15	140	105	85	16	4-19
50	230	203	160	125	100	16	4-18	152	120.5	82	16	4-19	155	120	100	16	4-19
65	290	215	180	145	120	18	4-18	178	139.5	105	17.5	4-19	175	140	120	18	4-19
80	310	241	195	160	135	20	8-18	190	152.5	127	19	8-19	185	150	130	18	8-19
100	350	292	215	180	155	20	8-18	229	190.5	157	24	8-19	210	175	155	18	8-19
125	400	330	245	210	185	22	8-18	254	216	166	24	8-23	250	210	185	20	8-23
160	480	356	280	240	210	24	8-23	279	241.5	216	25.4	8-23	280	240	215	22	8-23
200	550	496	306	296	265	26	12-23	343	298.5	270	29	4-23	360	295	270	22	12-23
250	560	622	405	355	320	30	12-25	406	362	324	30.5	12-25	400	355	325	24	12-25
300	750	698	460	410	375	30	12-25	483	431.8	361	32	12-25	445	400	370	24	16-25



内螺纹三通球阀
Female Three Way Ball Valve

DN	GE	d	L	H	W
8	1/4"	74	10	58	110
10	3/8"	74	12	58	110
15	1/2"	74	12	58	110
20	3/4"	84	15	60	120
25	1"	92	20	70	140
32	1 1/4"	124	25	82	140
40	1 1/2"	136	32	95	160
50	2"	154	38	100	200



二片式内螺纹球阀
Two-Piece Ball Valve




DN	G	d	g	L	E	H	W
8	1/4"	10	55	55	11.5	50	90
10	3/8"	12	55	60	11.5	50	90
15	1/2"	15	63	75	14	58	90
20	3/4"	20	73	80	15	62	110
25	1"	25	84	90	15	72	120
32	1 1/4"	32	98	110	18	80	130
40	1 1/2"	38	106	120	19	90	150
50	2"	50	121	140	19	90	170
65	2 1/2"	64	146	165	22	125	220
80	3"	78	166	205	25	138	240
100	4"	100	204	240	28	156	300

三片式内螺纹球阀
Three-Piece Ball Valve

DN	G	d	L	H	W
8	1/4"	10	65	50	90
10	3/8"	12	65	50	90
15	1/2"	15	70/75/81	55	100
20	3/4"	20	80/80/88	60	120
25	1"	25	90/90/98	70	140
32	1 1/4"	32	110/110/96	82	140
40	1 1/2"	38	120/120/104	90	180
50	2"	50	140/140/125	105	200
65	2 1/2"	64	160/165	120	220
80	3"	78	180/205	132	240
100	4"	100	215/240	160	300

一片式内螺纹球阀
One-Piece Ball Valve

DN	G	d	L	H	W
8	1/4"	5	40	28	70
10	3/8"	7	45	30	70
15	1/2"	9	55	34	90
20	3/4"	12	60	38	90
25	1"	15	70	50	110
32	1 1/4"	20	80	56	120
40	1 1/2"	25	86	60	130
50	2"	32	101	65	140
65	2 1/2"	38	117	72	170
80	3"	50	140	105	185



CHINA DONJOY TECHNOLOGY CO.,LTD.

DONJOY looking forward to your visit! Your telecommunications!



中国·东正 科技有限公司

地址: 温州空港经济技术开发区
温州滨海经济技术开发区
总机: 0577-86990888
传真: 0577-86998000

Add: Wenzhou airport economic and
technological development zone
Wenzhou binhai economic and
technological development zone
Tel: +86-577-86990888
Fax: +86-577-86998000
E-mail: donjoy@cndonjoy.com

www.cndonjoy.com

